



C.S. No. 1.
Excavation 802.6355 ft.

W. Level.

L. Level

1700

C.S. No. 2.
Excavation 500 ft.

O.D.

Total Excavation between C.S. No. 1 & 2. 20
 $= (802.635 + 500) / 2 \times 60 \times 22 \times 3$ cu yds. = 95526.6 cu yds.
 29 3

C.S. No. 3
Excavation 270.84 sq ft.
Bank work. 67.62 sq ft.

L.L.

O.D.

C.S. No. 4.
Excavation 138.155 sq ft.
Bank work. 192.87 sq ft.



Total Excavation between C.S. No. 2 & No. 4 = 457.2019 cu yds.
 " Bank work between C.S. No. 2 & No. 4. 5182.87 cu yds.

TOTAL EXCAVATION. 141246.79 cu yds.
 TOTAL BANKWORK 5182.87 "

Estimated cost.	21964.440	Excavation & Bank
	2560.666	Purchase of land
	500.00	coverage
	1700.00	Excavation of water
	<u>26025.046</u>	

Exclusive any work in Street, Currier and Verwoil's drawings.

